ADMINISTRATIVE MESSAGE

ROUTINE

R 180951Z JUL 96 ZYB PSN 567226M28

FM NAVAVNDEPOT NORTH ISLAND CA//4.8.7/3.1.4.4/4.0//

TO COMNAVAIRLANT NORFOLK VA//N422B40//
COMNAVAIRPAC SAN DIEGO CA//N22B3C//
COMNAVAIRESFOR NEW ORLEANS LA//N4243/N42715//
RUCBLFA/COMMARFORLANT//ALD-E//
COMMARFORPAC//ALD-E//
CNATRA CQ DETACHMENT//N422//
COMMARFORRES//ALD-E//
COMFAIRMED NAPLES IT//JJJ//
COMFAIRWESTPAC ATSUGI JA//JJJ//
CG FIRST MAW//ALD-E//
CG SECOND MAW//ALD-E//
RUWIKBC/CG THIRD MAW//ALD-E//
CG FOURTH MAW//ALD-E//

INFO COMNAVAIRSYSCOM WASHINGTON DC//AIR-3.6.1.4/PMA-251//
CMC WASHINGTON DC//JJJ//
ATKRON THREE FOUR//JJJ//

UNCLAS //N04790//

MSGID/GENADMIN/NAVAVNDEPOT NORIS CA/487LG//

SUBJ/SUPPORT EQUIPMENT BULLETIN (SEB) NO. 746, TD CODE 63, MOBILE
/FACILITY (MF) ELECTRICAL LOAD DECAL INSTALLATION//

REF/A/MOBILE FACILITIES/NEWSLETTER, DATED/29MARCH96//
POC/LLOYD BJURMAN/GS-11/CODE 487-4.8.7/LOC:NADEP NORIS CA
/TEL:DSN 735-5215/TEL:COML (619) 545-5215//

RMKS/1. COG CODE: NAVAVNDEPOT NORTH ISLAND CA, CODE 4.8.7.3.0.

2. CATEGORY: URGENT

3. DOCUMENTATION AFFECTED: NONE

4. PURPOSE: TO PROVIDE ONE TIME INSPECTION OF MOBILE FACILITY POWER DISTRIBUTION PANEL COVER TO DETERMINE IF PART NUMBER MFG245-3,

ELECTRICAL LOAD DECAL IS INSTALLED. THIS SEB PROVIDES INSTALLATION INSTRUCTIONS FOR PART NUMBER MFG245-3 DECAL IF REQUIRED.

5. APPLICATION:
(A) BASIC EQUIPMENT:

NOMENCLATURE	SERIAL NO.	QTY
MOBILE FACILITY	ALL	5000

(B) TRAINERS: N/A
(C) SPARES: N/A

6. COMPLIANCE:
(A) BASIC EQUIPMENT: INSTALLATION SHALL BE DONE AT THE ORGANIZATIONAL/INTERMEDIATE MAINTENANCE ACTIVITIES NO LATER THAN 60 DAYS AFTER BULLETIN ISSUE AND FULL COMPLIANCE NO LATER THAN 1 JULY 1997.
(B) TRAINERS: N/A
(C) SPARES: N/A

7. MAN HOURS:
(A) BASIC EQUIPMENT:

NO. OF MEN	SKILL	TOTAL MAN HRS.
1	AS (NAVY)/6XXX (MARINE CORPS)	0.2

(B) TRAINERS: N/A
(C) SPARES: N/A

8. SUPPLY DATA:
(A) REQUIREMENTS FOR BASIC EQUIPMENT:
(1) PARTS/MATERIALS REQUIRED:

QUANTITY	PART NUMBER	CAGE	NOMENCLATURE	SM&R	NSN
1	MFG245-3	91145	DECAL, ELECTRICAL LOAD	NONE	NONE

(2) PECULIAR SUPPORT EQUIPMENT REQUIRED: NONE
(3) DISPOSITION OF MATERIALS REMOVED: N/A
(4) SOURCE OF SUPPLY:
REQUISITION MATERIAL VIA MESSAGE, ADDRESSED TO: NAVAVNDEPOT, NORTH ISLAND, CA. CODE 3.1.4.4B OR PWC, NORFOLK, VA, CODE 30M.
(B) REQUIREMENTS FOR TRAINERS: N/A
(C) REQUIREMENTS FOR SPARES: N/A

9. REIDENTIFICATION: N/A

10. DETAILED INSTRUCTIONS:
A. INSPECT MF POWER DISTRIBUTION PANEL DOOR TO DETERMINE IF

ELECTRICAL LOAD DECAL (P/N MFG245-3) IS INSTALLED. IF NOT INSTALLED, COMPLETE FOLLOWING INSTRUCTIONS.

B. REQUISITION DECAL PER PARAGRAPH 8.

C. OBTAIN COPY OF REFERENCE (A) WHICH LISTS TOTAL KVA VALUES FOR MOST MFS. COPY OF REFERENCE (A) ELECTRICAL AND UTILITY REQUIREMENTS WILL BE SHIPPED WITH DECAL.

D. STENCIL OR WRITE THE TOTAL LOAD CONNECTED KVA VALUE FOR THE RESPECTIVE CONFIGURATION CODE ON THE DECAL IN BLACK, INDELIBLE INK.

E. ELECTRICAL LOAD INFORMATION NOT IN REFERENCE (A) CAN BE OBTAINED FROM ENGINEERING POC LISTED IN PARAGRAPH 15.

F. APPLY DECAL TO DOOR OF MAIN POWER DISTRIBUTION/CIRCUIT BREAKER PANEL ON MFS AND INUMFS. CENTER DECAL AND LOCATE THREE INCHES FROM TOP OF CIRCUIT BREAKER PANEL DOOR.

11. WEIGHT AND BALANCE: N/A

12. RECORDS AFFECTED:

A. ENTER COMPLIANCE IN SUPPORT EQUIPMENT CUSTODY AND MAINTENANCE HISTORY RECORD (OPNAV 4790/51).

B. COMPLIANCE SHALL BE REPORTED THROUGH THE VIDS/MAF OPNAV 4790/60 AND TECHNICAL DIRECTIVE STATUS ACCOUNTING SYSTEM.

13. VERIFIED BY: MALS-39, 3RD MAW, MCAS CAMP PENDLETON, CA.

14. RESCISSION DATE: 30 JUN 1998

15. RELATED INSTRUCTIONS:

A. REQUEST TYCOMS/LEAD ACTIVITIES PROVIDE WIDEST POSSIBLE DISSEMINATION.

B. POINT OF CONTACT FOR LOGISTICS SUPPORT IS MR. H. SALDIVAR, CODE 3.1.4.4B, DSN 735-4000 OR COMMERCIAL (619) 545-4000.

C. POINT OF CONTACT FOR ENGINEERING SUPPORT IS MR. L. BJURMAN, CODE 4.8.7.3.0, DSN 735-5215 OR COMMERCIAL (619) 545-5215.//

BT

*** MDS office codes that have received this message: ***

00EA2	3.1.8	3.6	4.1.9	8.0M
PMA251	ZMDSALL			